



DESCRIPTION: AAA Mobile Solutions 42-Bed Mobile Sleeper Units are built into 53' converted semi trailers. These units were designed to provide users with maximum comfort and amenities. Each of the 42 berths are complete with privacy curtains, 110v & USB plugs, reading lights, a convenience shelf, and a antimicrobial mattress.



Specifications & Features:

- 42 Individual private berths
- 32"x74.5" Antimicrobial mattresses
- Commercial fire alarm & c/o detector
- Blue sleep inducing lighting
- Exterior perimeter lighting
- Dual 3 ton HVAC system
- Adjustable vents in each berth
- (1) 110v & (2) USB plugs at each berth
- OSHA compliant steps and platforms
- Emergency crash door hardware
- Posted check in/check out roster board
- Optional fresh linen service available
- 53' length x 8.5' wide
- 120/208v 3-phase power
- On board 20kw generator
- Optional shore power connections
- 5 Hubbell single pole receptacles

